Index of Keynotes

KEYNOTE LEGEND MASTER

Key Value	Keynote Text
033000.A	CONCRETE FOOTING – REFER TO STRUCTURAL
033000.B	CONCRETE STRUCTURAL STOOP – REFER TO STRUCTURAL
033000.D	4" THICK CONCRETE SLAB ON GRADE – REFER TO STRUCTURAL
033000.E	VAPOR BARRIER OVER 6" GRANULAR FILL
033000.F	CAST-IN-PLACE CONCRETE WALL – REFER TO STRUCTURAL
033000.G	BOND BREAKER
034100.F	PRECAST STRUCTURAL STAIR ASSEMBLY
042000.C	THRU-WAL FLASHING ASSEMBLY – REFER TO DETAILS G1/A400 AND G4/A400
042000.C2	FLEXIBLE EPDM SHEET FLASHING
042000.C5	CAVITY DRAINAGE MATERIAL
042000.E	FACE BRICK – RUNNING BOND
042000.K2	FLEXIBLE EPDM SHEET FLASHING – INSTALL OVER ALL PANEL TO PANEL PRECAST JOINTS THAT FALL BEHIND MASONRY VENEER. FLASHING IS NOT IN LIEU OF BACKER ROD AND SEALANT BUT IS IN ADDITION TO
047200.A	CAST STONE WINDOW SILL – TYPE 1 – LIGHT SANDBLAST
047200.A2	CAST STONE WINDOW SILL – TYPE 2 – LIGHT SANDBLAST
047200.A3	CAST STONE WINDOW SILL – TYPE 3 – LIGHT SANDBLAST
047200.C	DRIP
047200.D	ALL CONNECTIONS TO BE DESIGNED AND PROVIDED BY CAST STONE SUPPLIER
054000.A	6" STEEL STUDS
054000.B	4" STEEL STUDS
055000.A	FABRICATED STEEL CANOPY ASSEMBLY
055100.B	PRE-ASSEMBLED STEEL PAN STAIR ASSEMBLY WITH CONCRETE FILLED TREADS – ARCHITECTURAL CLASS FOR EXPOSED CONSTRUCTION
055100.B2	STEEL TUBE STRINGER – REFER TO STRUCTURAL
055213.A	PAINTED STEEL GUARDRAIL ASSEMBLY
055213.A2	1 1/2" O.D. STEEL GUARDRAIL CAP
055213.A3	3/4" SQUARE VERTICAL STEEL GUARDRAIL PICKET
055213.A4	1 1/2" O.D. STEEL GUARDRAIL SUPPORT
055213.A5	1 1/2" O.D. STEEL GUARDRAIL BOTTOM RAIL
055213.B	1 1/2" O.D. STEEL HANDRAIL
055213.B2	HANDRAIL SUPPORT BRACKET
055213.C	PAINTED STEEL GUARDRAIL ASSEMBLY
055213.C2	1 1/2" O.D. STEEL GUARDRAIL CAP
055213.C3	1/2" SQUARE VERTICAL STEEL GUARDRAIL PICKET ATTACHED DIRECTLY TO TOP OF STRINGER
061600.C	5/8" THICK GLASS MAT WATER RESISTANT GYPSUM SUBSTRATE AS ACCEPTABLE BY ROOFING MANUFACTURER TO OBTAIN WARRANTY – APPLY TO BACKSIDE OF ALL FRAMED PARAPET ASSEMBLIES
064023.A	1/2" THICK SOLID SURFACE WINDOW SILL – RADIUS EXPOSED EDGE
064023.A2	1/2" THICK SOLID SURFACE COUNTER WITH 1 1/2" THICK FACE – EASE OUTSIDE EDGES
064023.M	5/8" OAK VENEERED PLYWOOD WITH OAK EDGE TRIM – RIFT CUT, FINISHED TO MATCH WOOD PANEL SYSTEM
071416.A	SINGLE-COMPONENT, POLYURETHANE WATERPROOFING SYSTEM
071416.C	2" THICK, UNFACED WALL-INSULATION DRAINAGE PANEL

KEYNOTE LEGEND MASTER

Key Value	Keynote Text
072100.D	CLOSED-CELL POLYURETHANE FOAM INSULATION
074216.A	FOAMED-INSULATION-CORE METAL WALL PANEL
075323.A	FULLY ADHERED ETHYLENE-PROPYLENE-DIENE-MONOMER (EPDM) ROOFING SYSTEM
075323.C	TERMINATION BAR
076200.B2	2-PIECE PRE-FINISHED ALUMINUM METAL COUNTERFLASHING
079200.A	SEALANT WITH BACKER ROD – REFER TO SPECIFICATIONS FOR SEALANT SCHEDULE
081416.A	SOLID CORE DOOR WITH WOOD VENEER FACE (FLUSH SLAB)
081416.B	SOLID CORE DOOR WITH WOOD VENEER FACE (FULL GLASS)
083113.A	24"x30" FIRE-RATED FLUSH ACCESS DOOR WITH CONCEALED FLANGE
084113.A	THERMALLY BROKEN ALUMINUM STOREFRONT ASSEMBLY – PROVIDE HEAVY WALL STOREFRONT WHERE NECESSARY TO RESIST APPLICABLE WIND LOADING
084113.A2	ALUMINUM STOREFRONT ASSEMBLY
084113.C	ALUMINUM DOOR
088000.B	IG-2: 1" CLEAR LOW-E INSULATING GLASS – PROVIDE FULLY TEMPERED AT LOCATIONS IDENTIFIED WITH "FT" AND WHERE REQUIRED BY CODE
088000.E	IG-3: 1" TINTED LOW-E INSULATING GLASS – PROVIDE FULLY TEMPERED AT LOCATIONS IDENTIFIED WITH "FT" AND WHERE REQUIRED BY CODE
088000.F	DG-1: 5/16" TEMPERED LAMINATED CLEAR GLASS WITH DECORATIVE PRINT
088000.G	DG-2: 1/4" FULLY TEMPERED FILM-FACED ART GLASS ASSEMBLY
088000.K	
092116.23.A	4" METAL STUDS
092116.23.B	1" TYPE X GYPSUM SHAFTLINER BOARD
092216.B	1 5/8" METAL STUDS
092216.C	3 5/8" METAL STUDS
092216.D	6" METAL STUDS
092900.A	5/8" TYPE X GYPSUM WALLBOARD – REFER TO SPECIFICATIONS FOR FURTHER DIRECTION REGARDING SPECIFIC LOCATION OF VARIOUS TYPES OF WALLBOARD
099123.A	PAINT
102113.A	TOILET ENCLOSURE
102113.B	URINAL SCREEN
102800.A	TOILET TISSUE DISPENSER
102800.B	GRAB BAR – 42" LENGTH
102800.B2	GRAB BAR – 36" LENGTH
102800.C	SANITARY NAPKIN DISPOSAL UNIT
102800.H	DIAPER CHANGING STATION
224000.D	DRINKING FOUNTAIN – REFER TO MECHANICAL
260500.A	BALLASTED SOLAR PANELS – REFER TO ELECTRICAL
312000.A	FREE DRAINING GRANULAR FILL
312000.B	IMPERVIOUS FILL
312000.C	COMPACTED BACKFILL
334600.A	
334600.B	

Code Summary

USE AND OCCUPANCY CLASSIFICATION

OCCUPANCY CLASSIFICATION

USE	**
USE	**
CONSTRUCTION TYPE:	**
Non-separated mixed use - Fully Sprinkled	

REQUIREMENTS BASED ON USE AND OCCUPANCY

SPECIAL OCCUPANCY REQUIREMENTS **

GENERAL BUILDING HEIGHTS AND AREAS

ALLOWABLE FLOOR AREA (Table 503)

Vicinity Map

Index of Drawings

Cover	Cover Sheet Interior Package
GENERAL	
G100	Code Review and Summary
G101	Drawing Standards
CIVIL	
1 of 1	Sanitary Sewer Plan
1 of 2	Public Paving Plan
C000	Site Plan
C100	Utility Plan
LANDSCAPE	
L100	Landscape Plan
ARCHITECTURAL	
A100	Basement Level Floor Plan
A101	First Level Demolition Plan
A102	Second Level Demolition Plan
A103	Ground Level Floor Plan
A104	Second Level Floor Plan
A105	Enlarged Floor Plans
A106	Schedules
A200	Exterior Demolition Elevations
A201	Exterior Elevations
A300	Wall Sections
A301	Wall Sections
A400	Enlarged Details
A401	Enlarged Details
A500	Aluminum Frame Types
A501	HM Frame Types, Door Types, Door Schedules
A502	Interior Elevations
A600	Interior Details
A700	Ground Level Reflected Ceiling Plan
A701	Second Level Reflected Ceiling Plan
A800	Floor Patterning Plan
A900	First Level Furnishing Plan
A901	Second Level Finish Plan
STRUCTURAL	
S100	Lower Level Foundation Plan
S200	Details
MECHANICAL	
M100	Lower Level Plan - Mechanical
M101	First Floor Plan - Mechanical
M102	Second Floor Plan - Mechanical
ELECTRICAL	
E001	Site Lighting Plan
E100	Basement Level Power Plan
E101	First Level Power Plan
E102	Second Level Power Plan
E200	Basement Level Lighting Plan
E201	First Level Lighting Plan
E202	Second Level Lighting Plan

—ARCHITECT—

Ryan Baker Cameron

6191 N 14th St.

Lincoln, NE 68521

T: 402 435 9203

Professional Seals

ARCHITECT

COORDINATING PROFESSIONAL

STRUCTURAL ENGINEER

MECHANICAL ENGINEER

ELECTRICAL ENGINEER

Project Consultants

STRUCTURAL ENGINEER
NAME
ADDRESS
CITY, STATE, ZIP
T: 402.477.7640

MECHANICAL/ELECTRICAL ENNAMEER
ADDRESS
Lincoln, NE 68508
T: 402.476.1273

CIVIL ENGINEER
NAME
ADDRESS
Lincoln, NE 68508

Bone Creek Musuem of Agrarian Art

855 D Street,
David City, NE 68632

August 30, 2013

13001

© Copyright RYAN BAKER CAMERON